

Public Meeting for

Horne Street Streetscape Improvements

CPN: 102764

Project Manager: Shweta Rao, PE, PMP

Project Engineer: Kimley-Horn and Associates, Inc.

July 6, 2023



Agenda


- Project Background
- Existing Condition and Proposed Improvements
- Schedule
- > Adjacent Projects
- > Questions





Project Background

- Federal funding awarded in August 2019
- Over \$8M in funding
- AFA executed with TxDOT in November 2020
- Kimley-Horn awarded design contract in January 2022.





Existing Conditions

2-lane street (20' lanes) Faded pavement markings Non-compliant sidewalks and curb ramps No existing bike lanes or on-street parking Dark Spots along the corridor









Proposed Improvements W. Vickery to Humbert:

- Upgraded traffic signal at W.
 Vickery and Horne Intersection
- Added midblock crosswalk with RRFB
- Improved/added sidewalks
- 2" Asphalt Overlay
- Added bike lane and buffer
- Additional landscape, trash receptacles, and benches will be provided along the corridor



Fort Worth Proposed Improvements Humbert to Kilpatrick

- Modified traffic signal at Libbey and Horne Intersection
- Added traffic signal at Goodman and Horne intersection
- Added designated left turn lane onto Libbey
 Avenue
- Improved/added sidewalks
- 2" Asphalt Overlay
- Added bike lane and buffer
- Additional landscape, trash receptacles, and benches will be provided along the corridor










Proposed Improvements Kilpatrick to Lovell

- From Geddes to Lovell-added
 6" Raised, Colored Concrete
 Median and On-Street Parking
- Improved/added sidewalks
- 2" Asphalt Overlay
- Added bike lane and buffer
- Additional landscape, trash receptacles, and benches will be provided along the corridor



Additional Improvement Evaluation

Roundabout at Libbey and Goodman

Intersection evaluation determined that adding a signal at Goodman that ties to Libbey was better for traffic operations.

Lighting Upgrades

FORT WORTH.

Photometric Analysis identified dark spots, therefore all light fixtures along the corridor will be updated to LED fixtures to improve light levels.

Signal at Houghton

Signal warrant analysis conducted, and the intersection did not warrant a traffic signal



Schedule

- Design complete– Winter 2024
- Construction start Winter 2025
- Substantial Completion Late 2027






Adjacent Projects



Camp Bowie at Horne Intersection Improvements



Camp Bowie at Bryant Irvin Intersection Improvements



Contact Information:

Shweta Rao, PE, PMP City Project Manager Shweta.Rao@fortworthtexas.gov Office Phone: 817-392-8022

Scott Arnold, PE Kimley-Horn Project Manager Scott.Arnold@kimley-horn.com Phone: 817-335-6511



Thank you all!!

