

Post Type FRP = Fiberalass Reinforced Plastic Pipe (see SMD(FRP)) TWT = Thin-Walled Tubing (see SMD(TWT))

10BWG = 10 BWG Tubing (see SMD(SLIP-1) to (SLIP-3)) S80 = Schedule 80 Pipe (see SMD(SLIP-1) to (SLIP-3))

Number of Posts (1 or 2) -

Anchor Type

UA - Universal Anchor - Concreted (see SMD(FRP) and (TWT)) UB = Universal Anchor - Bolted down (see SMD(FRP) and (TWT))

WS = Wedge Anchor Steel - (see SMD(TWT))

No more than 2 sign

posts should be located

within a 7 ft. circle.

WP - Wedge Anchor Plastic (see SMD(TWT))

SA = Slipbase - Concreted (see SMD(SLIP-1) to (SLIP-3)) SB = Slipbase - Bolted Down (see SMD(SLIP-1) to (SLIP-3))

Sign Wounting Designation

P = Prefab. "Plain" (see SMD(SLIP-1) to (SLIP-3), (TWT), (FRP)) T = Prefab. "T" (see SMD(SL]P-1) to (SL[P-3), (TWT)) U = Prefab. "U" (see SMD(SLIP-1) to (SLIP-3))

IF REQUIRED 1EXT or 2EXT = Number of Extensions (see SMD(SLIP-1) to (SLIP-3), (TWT)) BM = Extruded Wind Beam (see SMD(SLIP-1) to (SLIP-3))

WC = 1.12 #/ft Wing Channel (see SMD(SLIP-1) to (SLIP-3)) EXAL = Extruded Aluminum Sign Panels (see SMD(SL1P-3))

diameter

Single Signs

Sign Post

Bolts used to mount sign panels to the clamp are

5/16-18 UNC galvanized square head with nut,

bolt length is 1 inch for aluminum.

depending upon field conditions.

the universal clamp.

nylon washer, flat washer and lock washer. The

When two sign clamps are used to mount signs back-to-back, use a 5/16-18 UNC galvanized hex

right. The bolt length may need to be adjusted

Sign clamps may be either the specific size clamp

head per ASTM A307 with nut and helical-spring lock

washer. The approximate bolt lengths for various post

sizes and sign clamp types are given in the table at

U-bolt

Ѿ

Sian Panel

circle /

Not Acceptable

Nut. lock


washer

Nylon washer, flat

nut

washer. lock washer.

REQUIRED CLEARANCE FOR BREAKAWAY SUPPORT



To avoid vehicle undercarriage snagging, any substantial remains of a breakaway support, when it is broken away, should not project more than 4 inches above a 60-inch chord (i.e., typical space between wheel paths).

Acceptable

diameter

Back-to-Back

Signs

∕— Sign Panel

∠Sign Panel

Universal Clamp

3 or 3 1/2"

3 1/2 or 4"

4 1/2"

└ Sign Bolt

Approximate Bolt Length

Specific Clamp

3 or 3 1/2"

3 1/2 or 4"

diameter

circle

Nylon washer, flat

washer. lock washer.

Nylon washer, flat

washer. lock washer.


Pipe Diameter

2" nominal

2 1/2 nominal

3 nominal

TYPICAL SIGN ATTACHMENT DETAIL



LESS THAN 6 FT. WIDE

When the shoulder is 6 ft. or less in width, the sign must be placed at least 12 ft. from the edge of the travel lane.

HIGHWAY 6 ft min INTERSECTION AHEAD Greater than 6 ft 7.5 ft max Travel 7.0 ft min * Lone Payed Shou I der

SIGN LOCATION

GREATER THAN 6 FT. WIDE

When the shoulder is greater than 6 ft in width, the sign must be placed at least 6 ft, from the edge of the shoulder.

HIGHWAY

INTERSECTION

AHEAD

Concrete

Barrier

RESTRICTED RIGHT-OF-WAY

(When 6 ft min, is not possible,)

HIGHWAY

INTERSECTION

AHEAD

7.5 ft max

7.0 ft min

When this sign is needed at the end of a two-lane, two way roadway, the right edge of the sign should be in line with the centerline of the roodway. Place as close to ROW as practical.

Poved


Shou I der

T-INTERSECTION

- 6 ft min

7.5 ft max


7.0 ft min



Edge of Travel Lane

Travel

Lane



- * Signs shall be mounted using the following condition that results in the greatest sign elevation:
- (1) a minimum of 7 to a maximum of 7.5 feet above the edge of the travel lane or
- (2) a minimum of 7 to a maximum of 7.5 feet above the grade at the base of the support when sign is installed on the backslope.

The maximum values may be increased when directed by the Engineer.

See the Traffic Operations Division website for detailed drawings of sign clamps, Triangular Slipbase System components and Wedge Anchor System components.

The website address is http://www.txdot.gov/publications/traffic.htm

Payed

Shoul der


2 ft min**

Travel

possible


Travel


Paved



BEHIND CONCRETE BARRIER **Sign clearance based on distance required for proper guard rail or concrete barrier performance.

BEHIND BARRIER





Right-of-way restrictions may be created

7.5 ft max

7.0 ft min *

In situations where a lateral restriction prevents the minimum horizontal clearance from the edge of the travel lane, signs should be placed as far from the travel lane as practical.

Texas Department of Transportation Traffic Operations Division

SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS GENERAL NOTES & DETAILS

SMD (GEN) -08

	DN: TX	ют	CK# TXDOT	DW# TXDOT	CK# TXDOT	
· 08 REVISIONS	CONT	SECT	JOB		H[GHWAY	
	0902 0902	90 90	119 192		McCART	
	DIST	- ' 			SHEET NO.	
	FTW		TARRAN	٧T	133	


26A

diometer circle Not Acceptable BEHIND GUARDRAIL Not Acceptable SIGNS WITH PLAQUES CURB & GUTTER OR RAISED [SLAND

Shoul der by rocks, water, vegetation, forest, buildings, a narrow island, or other factors.

*** Post may be shorter if protected by guardrail or if Engineer determines the post could not be hit due to extreme


TRIANGULAR SLIPBASE INSTALLATION GENERAL REQUIREMENTS



NOTE

There are various devices approved for the Triangular Slipbase System. Please reference the Material Producer List for approved slip base systems. http://www.txdot.gov/business/producer list.htm The devices shall be installed per manufacturers' recommendations. Installation procedures shall be provided to the Engineer by Contractor.

CONCRETE ANCHOR



SM RD SGN ASSM TY XXXXX(X)SB(X-XXXX)

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. Heavy hex nut per ASTM A563, and hardened washer per ASTM F436. The stud bolt shall have a minimum yield and ultimate tensile strength of 50 and 75 KSI, respectively, Nuts, bolts and washers shall be galvanized per 11em 445, "Galvanizing. " Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxies and Adhesives. Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations. Top of bolt shall extend at least flush with top of the nut when installed. The anchor, when installed in 4000 psi normalweight concrete with a 5 1/2" minimum embedment, shall have a minimum allowable tension and shear of 3900 and 3100 psi, respectively.

GENERAL NOTES

- Slip base shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to approval of the TxDOT Traffic Standards Engineer.
- 2. Material used as post with this system shall conform to the following specifications:

10 BWG Tubing (2.875" outside diameter) 0.134 nominal wall thickness

Seamless or electric-resistance welded steel tubing or pipe Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008

Other steels may be used if they meet the following:

55,000 PS1 minimum yield strength

70,000 PSI minimum tensile strength 20% minimum elongation in 2"

Wall thickness (uncoated) shall be within the range of 0,122" to 0,138" Outside diameter (uncoated) shall be within the range of 2.867" to 2.883"

Galvanization per ASTM A123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat

tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.

Schedule 80 Pipe (2.875" outside diameter)

0.276 nominal wall thickness

Steel tubing per ASTM A500 Gr C

Other seamless or electric-resistance welded steel tubing or pipe with equivalent outside diameter and wall thickness may be used if they meet the followings

46,000 PS1 minimum yield strength
62,000 PS1 minimum tensile strength

21% minimum elongation in 2"

Wall thickness (uncoated) shall be within the range of 0.248" to 0.304"

Outside diameter (uncoated) shall be within the range of 2.855" to 2.895" Galvanization per ASTM A123

3. See the Traffic Operations Division website for detailed drawings of sign clamps and Texas

- Universal Triangular Slipbase System components. The website address is: https://www.txdot.gov/publications/traffic.htm
- 4. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

ASSEMBLY PROCEDURE

Foundation

- 1. Prepare 12-inch diameter by 42-inch deep hole. If solid rock is encountered, the depth of the foundation may be reduced such that it is embedded a minimum of 18 inches into the solid rock.
- 2. The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor-driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- 3, Push the pipe end of the slip base stub into the center of the concrete. Rotate the stub back and forth while pushing it down into the concrete to assure good contact between the concrete and stub. Continue to work the stub into the concrete until it is between 2 to 4 inches above the ground.
- 4. Plumb the stub. Allow a minimum of 4 days to set, unless otherwise directed by the Engineer.
- 5. The triangular slipbase system is multidirectional and is designed to release when struck from any

1. Cut support so that the bottom of the sign will be 7 to 7.5 feet above the edge of the travelway (i.e., edge of the closest lane) when slip plate is below the edge of pavement or 7 to 7.5 feet above slip plate when the slip plate is above the edge of the travelway. The cut shall be plumb and

26B

2. Attach sign to support using connections shown. When multiple signs are installed on the same support, ensure the minimum clearance between each sign is maintained. See SMD(SLIP-2) for clearances based on sign types.




SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD (SL IP-1) - 08

	DNI TXD	ют	CK# TXDOT	D₩a	TXDOT	CK# TXDOT	
9-08 REVISIONS	CONT	SECT	JOB			H [CHWAY	
	0902 0902	90 90	119 192		M	IcCART	
	DIST		COUNTY			SHEET NO.	
	FTW		TARRAN	1T		134	







GENERAL NOTES

Top View

Detail B

3/8" x 3 1/2" heavy hex

A307 galvanized per

Item 445 Galvanizing.

bolt with nut, lock washer

and 2 flat washers per ASTM

T&U Bracket

1/2" x 4" heavy

hex bolt, nut, lock

washer and 2 flat

washers per ASTM

"Galvanizing."

Detail E

Sign Clamp

Universal)

(Specific or

A307 galvanized per

Wing

11

-11

8

U-Bracket

Channe

١.	SIGN SUPPORT	<pre># OF POSTS</pre>	MAX. SIGN AREA
	10 BWG	1	16 S F
	10 BWG	2	32 SF
	Sch 80	1	32 SF
	Sch 80	2	64 SF

The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.

3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.

 Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
5. Signs that require specific supports due to reasons

in addition to windloading are indicated on the

"REQUIRED SUPPORT" table on this sheet.
6. For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of

greater height.
7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.

8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be

galvanized per ASTM A 123.

9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."

10.Additional route markers may be added vertically,

provided the total sign area does not exceed the maximum allowable amount per Note 1.


11. Additional sign clamp required on the "T-bracket" post

for 24 inch height signs. Place the clamp 3 inches above

bottom of sign when possible.

12.Post open ends shall be fitted with Friction Caps.

13. Sign blanks shall be the sizes and shapes shown on the





SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEMİ

SMD (SL IP-2) -08


CTxDOT July 2002	DNI TX	ют	CK# TXDOT	DWa	TXDOT	CK# TXDOT	
9-08 REVISIONS	REVISIONS CONT SECT JOE		JOB	HEG		CHWAY	
	0902 0902	90 90	119 192		Мс	CART	
	DIST		COUNTY			SHEET NO.	
	FTW	TARRANT				135	


and show no evidence of metal fracture. Caps shall have an electrodeposited coating of zinc in accordance with the requirements of ASTM


B633 Closs FE/ZN 8.


025 ± 010


0
















SM RD SGN ASSM TY S80(2)XX(P-EXAL)

* Additional stiffener placed at approximate center of signs when sign width is greater than 10'.





Use Extruded Alum. Windbeam as stiffeners See SMD (2-1) for additional details

See Detail E for clamp installation

GENERAL NOTES

1.	SIGN SUPPORT	# OF POSTS	MAX. SIGN AREA
	10 BWG	1	16 S F
	10 BWG	2	32 SF
	Sch 80	1	32 SF
	Sch 80	2	64 SF

- The Engineer may require that a Schedule 80 post be used in place of a 10 BWG where a sign height is abnormally high due to a fill slope.
- 3. Sign supports shall not be spliced except where shown. Sign support posts shall not be spliced.
- Aluminum sign blanks shall conform to Departmental Material Specifications DMS-7110 and shall have the following minimum thicknesses: 0.080 for signs less than 7.5 sq. ft., 0.100 for signs 7.5 to 15 sq. ft., and 0.125 for signs greater than 15 sq. ft.
 5. Signs that require specific supports due to reasons
- in addition to windloading are indicated on the "REQUIRED SUPPORT" table on this sheet.
- For horizontal rectangular signs fabricated from flat aluminum, T-brackets are used for signs 24 inches or less in height. U-brackets are used for signs of
- greater height.
 7. When two triangular slipbase supports are used to support a single sign, they shall not be "rigidly connected to each other except through the sign panel. This will allow each support to act independently when impacted by an errant vehicle.
- 8. Wing channel shall meet ASTM A 1011 SS Gr 50 and be
- galvanized per ASTM A 123.

 9. Excess pipe, wing channel, or windbeam shall be cut off so that it does not extend beyond the sign panel (i.e., excess support shall not be visible when the sign is viewed from the front.) Repair galvanized coating at cut support ends per Item 445, "Galvanizing."
- 10. Sign blanks shall be the sizes and shapes shown on
- 11. Additional sign clamp required on the "T-bracket" post for 24 inch high signs. Place the clamp 3 inches above bottom of sign when possible.
- 12. Post open ends shall be fitted with Friction Caps.


	REQUIRED SUPPORT								
	SIGN DESCRIPTION	SUPPORT							
	48-Inch STOP sign (R1-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)							
Regulatory	60-inch YIELD sign (R1-2)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)							
	48x16-inch ONE-WAY sign (R6-1)	TY 10BWG(1)XX(T) TY 10BWG(1)XX(P-BM)							
Regu	36x48, 48x36, and 48x48-inch signs	TY 10BWG(1)XX(T)							
	48x60-inch signs	TY S80(1)XX(T)							
	48x48-inch signs (diamond or square)	TY 10BWG(1)XX(T)							
ğ	48x60-inch signs	TY S80(1)XX(T)							
Warning	48-inch Advance School X-ing sign (S1-1)	TY 10BWG(1)XX(T)							
W	48-inch School X-ing sign (S2-1)	TY 10BWG(1)XX(T)							
	Large Arrow sign (W1-6 & W1-7)	TY 10BWG(1)XX(T)							



SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS TRIANGULAR SLIPBASE SYSTEM

SMD (SL IP-3) -08

(C) Tx[0 1 July 2002	DNI TXD	ют	CK# TXDOT	DWa	TXDOT	CK# TXDOT	
9-08 REVISIONS		CONT	SECT	JOB	JOB		HIGHWAY	
5 00			90 90	119 192		M	1cCART	
		DIST		COUNTY			SHEET NO.	
		FTW		TARRAN	<u>IT</u>		136	



Wedge Anchor High Density Polyethy lene (HDPE) System


Friction Cap

or Plug. See


detail on SMD

-12" Dia


SM RD SGN ASSM TY TWT(X)UA(P)




Universal Anchor System with Thin-Walled Tubing Post




Plastic insert must be used when using the TWT with either the Universal Anchor System or the Bolt Down Universal Anchor System. The insert should be approx. 10" long and cover the tubing from just above the top of the stub pipe to the bottom of the sign post when using the Universal Anchor System. The insert should be cut to approx. 4 1/2" when used with the Bolt Down Universal Anchor System.




Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. A heavy hex nut per ASTM A563 and hardened washer per ASTM F436. The stud bolt shall have minimum yield and ultimate tensile strengths of 50 and 75 ksi, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Top of bolt shall extend at least flush with top of nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 3 3/8" minimum embedment, shall have a minimum allowable tension and shear of 2450 and 1525 psi, respectively. Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxies and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations.



Sign Installation Using a Prefabricated T-Bracket for Thin-Wall Tubing Post





9/16" hole may need to be drilled through post to accommodate bolt.

NOTE

The devices shall be installed per manufacturer's recommendations. Installation procedures shall be provided to the Engineer by Contractor.

GENERAL NOTESI

- 1. The Wedge Anchor System and the Universal Anchor System with thin wall tubing post may be used to support up to 10 square feet of sign area.
- 2. The tubular socket, wedge and prefabricated I-bracket shall be permanently marked to indicate manufacturer. Method, design, and location of marking are subject to the approval of the TxDOT Traffic Standards Engineer.
- 3. Except for posts (13 BWG Tubing), clamps, nuts and bolts, all components shall be pregualified. A list of pregualified vendors may be obtained from the Material Producer List web page. The website address is:
- http://www.txdot.gov/business/producer list.htm Material used as post with this system shall conform to the following specifications: 13 BWG Tubing (2.375" outside diameter) (TWT)

0.095" nominal wall thickness

Seamless or electric-resistance welded steel tubing Steel shall be HSLAS Gr 55 per ASTM A1011 or ASTM A1008 Other steels may be used if they meet the followings

55,000 PSI minimum yield strength 70,000 PSI minimum tensile strength

18% minimum elongation in 2"

"Wall thickness (uncoated) shall be within the range of .083" to .099" Outside diameter (uncoated) shall be within the range of 2.369" to 2.381" Galvanization per ASTM 123 or ASTM A653 G210. For precoated steel tubing (ASTM A653), recoat tube outside diameter weld seam by metallizing with zinc wire per ASTM B833.

- 5. Sign blanks shall be the sizes and shapes shown on the plans.
- 6. Additional sign clamp required on the "T-bracket" post for 24" high signs. Place clamp at least 3" above bottom of sign when possible.
- 7. Sign supports shall not be spliced except where shown. Sign support posts shall
- 8. See the Traffic Operations Division website for detailed drawings of sign clamps and Wedge Anchor System components. The website address is: http=//www.txdot.gov/publications/traffic.htm

WEDGE ANCHOR SYSTEM INSTALLATION PROCEDURE

- 1. Dig foundation hole. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18° or provide a minimum foundation depth of 30°. If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- 2. The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Place concrete into hole until it is approximately flush with the ground. Concrete shall be Class A.
- 3. Insert tubular socket into concrete until top of socket is approximaely 1/4 " above the concrete footing.
- 4. Plumb the socket. Allow a minimum 4 days for concrete to set, unless otherwise directed by Engineer...
- 5. Attach the sign to the sign post.
- 6. Insert the sign post into socket and align sign face with roadway.
- 7. Drive the wedge into the socket to secure post. This will leave approximately 3 inches of the wedge exposed.

UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURE

- 1. Dig foundation hale. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- 2. Insert base post in hole to depths shown and backfill hole with concrete.
- 3. Level and plumb the base post using a torpedo level and allow concrete adequate time to set. The bottom of the slots provided in the stub pipe shall remain above the top of the concrete foundation.
- 4. Attach the sign to the sign post.
- 5. Install plastic insert around bottom of post.
- 6. Insert sign post into base post. Lower until the post comes to rest on steel rod. 7. Seat compression ring using a hommer. Typically, the top of compression ring
- will be approximately level with top of stub post when optimally installed.
- 8. Check sign post by hand to ensure it is unable to turn. If loose, increase the tightening of the compression ring.



SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS WEDGE & UNIVERSAL ANCHOR WITH THIN WALL TUBING POST SMD (TWT) -08

	DNI TX	ют	CK# TXDOT DW# TXDOT		TXDOT	CK# TXDOT	
-08 REVISIONS	CONT	SECT	JOB	H [CHW		CHWAY	
	0902 0902	90 90	119 192		Мс	CART	
	DIST		COUNTY			SHEET NO.	
	FTW	TARRANT				137	

Friction Cap

or Plug. See

detail on SMD

(Slip-2)

Universal Anchor System with Fiberglass Reinforced Plastic (FRP) Post

slots (4

Fiberglass


Plastic


Schedule 40

(3 Nominal

Stub Pine

equally







5/8" diameter Concrete Anchor - 4 places (embed a min, of 3 3/8" and torque to min, of 50 ft-lbs). Anchor may be expansion or adhesive type.

Concrete anchor consists of 5/8" diameter stud bolt with UNC series bolt threads on the upper end. A heavy hex nut per ASTM A563 and hardened washer per ASTM F436. The stud bolt shall have minimum yield and ultimate tensile strengths of 50 and 75 ksi, respectively. Nuts, bolts and washers shall be galvanized per Item 445, "Galvanizing." Top of bolt shall extend at least flush with top of nut when installed. The anchor, when installed in 4000 psi normal-weight concrete with a 3 3/8" minimum embedment, shall have a minimum allowable tension and shear of 2450 and 1525 psi, respectively. Adhesive type anchors shall have stud bolts installed with Type III epoxy per DMS-6100, "Epoxies and Adhesives." Adhesive anchors may be loaded after adequate epoxy cure time per the manufacturer's recommendations.

BOLT-DOWN DETAILS







SM RD SGN ASSM TY FRP(X)UB(P)

Typical Sign Mounting Detail for FRP Support with Single Sign

SM RD SGN ASSM TY FRP(X)UA(P)



Typical Sign Mounting Detail for FRP Support with Back-to-Back Signs



GENERAL NOTES

- FRP sign supports for a single type sign support may be used for signs up to and including 16 square feet. Dual post installation may be used for signs up to and including 32 square feet.
- 2. All nuts, bolts and washers shall be galvanized per [tem 445, "Galvanizing."
 3. See the Traffic Operations Division website for detailed drawings of sign
- clamps. The website address is http://www.txdot.gov/publications/traffic.htm

FRP POST REQUIREMENTS

- Materials shall conform to the requirements of Departmental Material Specification DMS-4410 and will be furnished in a yellow or gray color as specified elsewhere in the plans.
- 2. Thickness of FRP sign support is 0.125" 0.031", 0.0".
- FRP sign supports are prequalified by the Traffic Operations Division.
 Prequalification procedures are obtained by writing:
 Texas Department of Transportation

Traffic Operations Division
125 East 11th Street
Austin, Texas 78701-2483

UNIVERSAL ANCHOR SYSTEM INSTALLATION PROCEDURES

- 1. Dig foundation hale. Where solid rock is encountered at ground level, the foundation shall be a minimum depth of 18". When solid rock is encountered below ground level, the foundation shall extend in the solid rock a minimum depth of 18" or provide a minimum foundation depth of 30". If solid rock is encountered, the socket/stub may be reduced in length as required to a minimum length of 18". Any material removed from the socket/stub shall be from the bottom and the clearance requirements given on SMD(GEN) must be followed. The inner surfaces of the socket/stub must remain free of concrete or other debris.
- The Engineer may permit batches of concrete less than 2 cubic yards to be mixed with a portable, motor driven concrete mixer. For small placements less than 0.5 cubic yards, hand mixing in a suitable container may be allowed by Engineer. Concrete shall be Class A.
- Insert base post in foundation hale to depths shown and fill hale with concrete. Cut base post from bottom and ensure a minimum of 18" embedment if installed in solid rock.
- 4. Level and plumb the base post with coupler using a torpedo level and let concrete set a minimum of 4 days, unless otherwise directed by Engineer, Bottom of base post slots shall be above the concrete footing.
- 5. Attach sign to FRP post.
- Insert sign post into base post. Lower until the post comes to rest on the steel rod.
- 7. Use hammer to ensure the coupler is firmly seated. Top of coupler should be level with top of base post in most instances.
- 8. Check sign to ensure there is no twist. If loose, increase the tightening of coupler.

BOLT DOWN SIGN SUPPORT


- 1. Position bose plate with coupler on existing concrete.
- 2. Drill holes into concrete and insert the $5/8\,^{\circ}$ diameter bolts with wedge anchors, and tighten nuts.
- 3. Attach sign to FRP post.
- 4. Insert bottom of sign post into pipe stub.
- Use hammer to ensure the coupler is firmly seated. Top of coupler should be level with top of base post in most instances.
- Check sign to ensure there is no twist. If loose, increase the tightening of coupler,



SIGN MOUNTING DETAILS SMALL ROADSIDE SIGNS UNIVERSAL ANCHOR SYSTEM WITH FRP POST

SMD (FRP) -08

© TxDOT July 200	2 DNI TXD	DNI TXDOT		DWa T	TXDOT	CK# TXDOT
9-08 REVISIONS	CONT	SECT	JOB		нго	HWAY
	0902 0902	90 90	119 192		McCART	
	DIST	COUNTY		COUNTY		HEET NO.
	FTW		TARRAN	١T		138



CFW MON 8309 N 6919862.06 E 2318060.05 EL = 743.06

> CP #50 CAPPED IRON ROD SET N 6921186.88 E 2317156.84 EL = 749.04

CP #51 CAPPED IRON ROD SET N 6921134.48 E 2317579.18 EL = 738.81 CP #52 CAPPED IRON ROD SET N 6921682.87 E 2317470.30 EL = 745.02

CP #53 CAPPED IRON ROD SET N 6921270.05 E 2316408.30 EL = 769.59

CP #54 CAPPED IRON ROD N 6920747.07 E 2316690.13 758.90



100 200 3

GRAPHIC SCALE IN FEET

---NOT FOR CONSTRUCTION---

THIS DOCUMENT HAS BEEN RELEASED FOR THE PURPOSE OF INTERIM REVIEW UNDER THE AUTHORITY OF ERIC A. CANALES P.E. 90103 IT IS NOT TO BE USED FOR CONSTRUCTION PURPOSES.

---NOT FOR CONSTRUCTION---



2821 WEST 7TH ST SUITE 400 FORT WORTH, TEXAS 76107 (817) 877-5571 TBPE Reg #F351

Texas Department of Transportation

STORM WATER POLLUTION PREVENTION PLAN

	FED.RD. DIV.NO.	STAT	SHEET NO.	
	6	SEE		
REVISIONS	STATE	DISTRICT	COUNTY	139
	TEXAS	FTW		
	CONTROL	SECTION	JOB	HIGHWAY NO.
	0902 0902	90 90	119 192	McCART
	0902		119	NO.

Connect the ends of the successive reinforcement sheets or rolls a minimum of 6 times with hog rings.

Hardwood posts shall have a minimum cross section of 1.5" x 1.5" Fasten fabric to the top strand of the wire using

4' minimum steel or wood posts spaced at 6' to 8'.

hog rings or cord at a maximum spacing of 15".

Softwood posts shall be 3" minimum in diameter or nominal 2" x 4".

Attach the wire mesh and fabric on end posts using 4 evenly spaced staples for wooden posts (or 4 T-Clips or

Galvanized welded wire mesh (W.W.M.) (12.5 GA, SWG Min.) with a maximum opening size of 2"x 4"or Woven Mesh (W.M.) (See woven mesh option detail)


sewn vertical pockets for steel posts).

Place 4" to 6" of fabric against the trench side and approximently 2" across the trench bottom in the upstream direction.

Minimum trench size shall be 6" square. Backfill and hand tamp.

TEMPORARY SEDIMENT CONTROL FENCE

Woven filter fabric —



HINGE JOINT KNOT WOVEN MESH (OPTION) DETAIL

Galvanized hinge joint knot woven mesh (12.5 GA.SWG Min.) requires a minimum of five horizontal wires spaced at a maximum of 12 inches apart and all vertical wires spaced at a maximum of 12 inches apart.

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.


Sediment control fence should be sized to filter a maximum flow through rate of 100 GPM/FT². Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.

LEGEND

Sediment Control Fence -(SCF)-

GENERAL NOTES

- 1. Vertical tracking is required on projects where soil distributing activities have occurred unless otherwise approved.
- 2. Perform vertical tracking on slopes to temporarily stabilize soil.
- 3. Provide equipment with a track undercarriage capable of producing linear soil impressions measuring a minimum of 12" in length by 2" to 4" in width by 1/2" to 2" in depth.
- 4. Do not exceed 12" between track impressions.
- 5. Install continous linear track impressions where the minimum 12" length impressions are perpendicular to the slope or direction of water flow.




VERTICAL TRACKING




TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES FENCE & VERTICAL TRACKING

EC(1)-16

FILE: ec116	DN# TxD	OT	CK1KM DWIVP		DN/CKI LS	
C TxDOT: JULY 2016	CONT	SECT	JOB		HIGHWAY	
REVISIONS	0902 0902	90 119 90 192		M	McCART	
	DIST	COUNTY			SHEET NO.	
	FTW	TARRANT			140	



PLAN VIEW




ELEVATION VIEW

CONSTRUCTION EXIT (TYPE 1)


ROCK CONSTRUCTION (LONG TERM)

GENERAL NOTES (TYPE 1)

- The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
- 2. The coarse aggregate should be open graded with a size of 4" to 8".
- The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other materialas approved by the Engineer.
- The construction exit shall be graded to allow drainage to a sediment trapping device.
- 6. The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



PLAN VIEW




ELEVATION VIEW

CONSTRUCTION EXIT (TYPE 2)

TIMBER CONSTRUCTION (LONG TERM)


GENERAL NOTES (TYPE 2)

- The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50'.
- The treated timber planks shall be attached to the railroad ties with ½"x 6" min. lag bolts. Other fasteners may be used as approved by the Engineer.
- The treated timber planks shall be *2 grade min., and should be free from large and loose knots.
- 4. The approach transitions shall be no steeper than 6:1 and constructed as directed by the Engineer.
- 5. The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- The construction exit should be graded to allow drainage to a sediment trapping device.
- 7. The guidelines shown hereon are suggestions only and may be modified by the Engineer.
- Construct exits with a width of at least 14 ft. for one-way and 20 ft. for two-way traffic for the full width of the exit, or as directed by the engineer.



Paved Roadway

PLAN VIEW



SECTION A-A CONSTRUCTION EXIT (TYPE 3) SHORT TERM

GENERAL NOTES (TYPE 3)

- The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
- The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
- The treated timber planks shall be *2 grade min., and should be free from large and loose knots.

© **T**×DOT

4. The guidelines shown hereon are suggestions only and may be modified by the Engineer.



Design Division Standard

141

TEMPORARY EROSION,
SEDIMENT AND WATER
POLLUTION CONTROL MEASURES
CONSTRUCTION EXITS

LC(3) 10									
:316	DN: <u>TxD</u>	<u>10</u>	ск: КМ	DW:	VP	DN/CK: LS			
T: JULY 2016	CONT	SECT	JOB			HIGHWAY			
REVISIONS	0902 0902	90 90	119 192		N	IcCART			
	DIST		COUNTY			SHEET NO.			

TARRANT

FC(3)-16

F: 5/4/3

TEMP. EROSION FLOW CONTROL LOG ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE LOG ON DOWNHILL STAKE AS SIDE AT THE CENTER, DIRECTED AT EACH END, AND AT ADDITIONAL POINTS AS NEEDED TO SECURE LOG (4' MAX. SPACING), OR AS DIRECTED BY THE ENGINEER.

PLAN VIEW

FLOW ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS SECURE END OF LOG TO STAKE AS DISTURBED AREA DIRECTED BACK OF CURB LIP OF GUTTER STAKE ON DOWNHILL SIDE OF TEMP. EROSION LOG AT 8' (ON CENTER) MAX. CONTROL LOG AS NEEDED TO SECURE LOG, OR AS DIRECTED BY THE ENGINEER.

STAKE ON DOWNHILL SIDE OF LOG AT 8' (ON CENTER) MAX. AS NEEDED TO SECURE LOG, (TYP.) OR AS DIRECTED BY THE ENGINEER. R. O. W. TEMPORARY EROSION CONTROL LOG FLOW -DISTURBED AREA SECURE END BACK OF CURB OF LOG TO STAKE AS DIRECTED LIP OF GUTTER ADDITIONAL UPSTREAM STAKES FOR HEAVY RUNOFF EVENTS

PLAN VIEW

TEMP. EROSION R.O.W. CONTROL LOG COMPOST CRADLE UNDER EROSION CONTROL LOG STAKE SECTION C-C

1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.

GENERAL NOTES:

2. LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.

UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS. USE RECYCLABLE CONTAINMENT MESH.

FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.

STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR. 2'-4' LONG. EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY THE ENGINEER.

DO NOT PLACE STAKES THROUGH CONTAINMENT MESH.


COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.

SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.

TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE TO PREVENT RUNOFF FROM FLOWING AROUND THE

10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

PLAN VIEW



TEMP. EROSION CONTROL LOG R. O. W. COMPOST CRADLE UNDER EROSION CONTROL LOG

SECTION B-B EROSION CONTROL LOG AT BACK OF CURB (CL-BOC)


EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY



MINIMUM COMPACTED DIAMETER MINIMUM COMPACTED DIAMETER

DIAMETER MEASUREMENTS OF EROSION CONTROL LOGS SPECIFIED IN PLANS

SHEET 1 OF 3




TEMPORARY EROSION. SEDIMENT AND WATER POLLUTION CONTROL MEASURES

EROSION CONTROL LOG

EC(9)-16

FILE: ec916	DN#TxDOT		ска КМ	DWI	LS/PT	CK1 LS		
C TxDOT: JULY 2016	CONT	SECT	JOB		H1GHWAY			
REVISIONS	0902 0902	90 90	90 119 90 192			McCART		
	DIST	COUNTY				SHEET NO.		
	FTW		TARRAN	ΙT		142		



REBAR STAKE DETAIL

LEGEND

- CL-D ─ EROSION CONTROL LOG DAM
- -(cl-boc)- EROSION CONTROL LOG AT BACK OF CURB

SECTION A-A

EROSION CONTROL LOG DAM

CL-D

- EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY (CL-ROW)
- EROSION CONTROL LOGS ON SLOPES STAKE AND TRENCHING ANCHORING -(CL-SST
- EROSION CONTROL LOGS ON SLOPES STAKE AND LASHING ANCHORING (CL-SSL
- (CL-DI) — EROSION CONTROL LOG AT DROP INLET
- (CL-CI EROSION CONTROL LOG AT CURB INLET
- (cl-gi)— EROSION CONTROL LOG AT CURB & GRATE INLET

SEDIMENT BASIN & TRAP USAGE GUIDELINES

An erosion control log sediment trap may be used to filter sediment out of runoff draining from an unstabilized area.


The drainage area for a sediment trap should not exceed Log Traps: 5 acres. The trap capacity should be 1800 CF/Acre (0.5" over the drainage area).

Control logs should be placed in the following locations:

- 1. Within drainage ditches spaced as needed or min. 500' on center
- 2. Immediately preceding ditch inlets or drain inlets 3. Just before the drainage enters a water course
- 4. Just before the drainage leaves the right of way
- 5. Just before the drainage leaves the construction limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a depth of 1/2 the log diameter.

Cleaning and removal of accumulated sediment deposits is incidental and will not be paid for separately.



Design Division Standard

HIGHWAY

McCART SHEET NO.

TARRANT


SECURE END OF LOG TO STAKE AS DIRECTED

TEMP. EROSION CONTROL LOG

EROSION CONTROL LOG AT CURB & GRADE INLET

EROSION CONTROL LOG AT DROP INLET

(CL-DI)



OVERLAP ENDS TIGHTLY 24" MINIMUM

COMPLETELY SURROUND
DRAINAGE ACCESS TO
AREA DRAIN INLETS WITH
EROSION CONTROL LOG

FLOW


-STAKE OR USE SANDBAGS ON DOWNHILL SIDE OF LOG AS NEEDED TO HOLD IN PLACE (TYPICAL)

EROSION CONTROL LOG AT CURB INLET

CURB


TEMP. EROSION CONTROL LOG

SANDBAG



(CL -C I)


(CL-CI)




NOTE: EROSION CONTROL LOGS USED AT CURB INLETS SHOULD ONLY BE USED IF THEY WILL NOT IMPEDE

2 SAND BAGS


TEMP. EROSION CONTROL LOG



USE STAKES ON DOWNSTREAM SIDE OF LOGS, AT ENDS, MIDPOINT, & AS NEEDED OR SANDBAGS TO HOLD IN PLACE.



SANDBAG DETAIL



CURB INLET _INLET EXTENSION

- 2 SAND BAGS

TEMPORARY EROSION, SEDIMENT AND WATER

POLLUTION CONTROL MEASURES **EROSION CONTROL LOG**

EC(9) - 16

	• •	•	•					
E: ec916	DN∎TxDOT		CKa	KM	DWI	LS/PT	• [CKI LS
TxDOT: JULY 2016	CONT	SECT		JOB			HIGH	YAW
REVISIONS	0902 0902	90 90		119 192		V	ΛсС	ART
	DIST	COUNTY					SHEET NO.	
	FTW		TA	RRAN	ΙT			144

A. GENERAL SITE DATA

1. PROJECT LIMITS: Highway: McCart Ave From: Altamesa Blvd Intersection To: Altamesa Blvd Intersection

LATTITUDE: 32°58'59-19"N

LONGITUDE: 97°22'02.79'W

2. PROJECT SITE MAPS:

- * Project Location Map: Title Sheet (Sheet I)
- * Drainage Patterns: Drainage Area Maps (Sheets 77-80)
- * Approx. Slopes Anticipated After Major Gradings and Areas of Soil Disturbance: Typical Sections (Sheets 7-8)
- * Major Controls and Locations of Stabilization Practices: (Sheets 139) SW3P Site Map Sheets
- * Project Specific Locations:

To be specified by Project Field Office and located in the Project SW3P File * Surface Waters and Discharge Locations: Drainage and Culvert Layout Sheets

(Sheets 77-80)

3. PROJECT DESCRIPTION:

For the construction of traffic signal intersection

4. MAJOR SOIL DISTURBING ACTIVITIES:

Grading and paving

5. EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

10% native Texas Grases,90% no vegitation - pavement, walks and drives

6. TOTAL PROJECT AREA: 234 Acres

7. TOTAL AREA TO BE DISTURBED: 0.3 Acres (14% OF TOTAL PROJECT AREA)

8. WEIGHTED RUNOFF COEFFICIENT

BEFORE CONSTRUCTION: AFTER CONSTRUCTION:

9. NAME OF RECEIVING WATERS:

Channelized to Edgecliff Branch

10. ENDANGERED SPECIES, DESIGNATED CRITICAL HABITAT AND HISTORIC PROPERTY:

No Endangered Species, Designated Critical Habitat or Historic Property has been found on this project site.

B. EROSION AND SEDIMENT CONTROLS

1. SOIL STABILIZATION PRACTICES:

____ PRESERVATION OF NATURAL RESOURCES ____ TEMPORARY SEEDING ____ FLEXIBLE CHANNEL LINER MULCHING (Hay or Straw) _ BUFFER ZONES ____ RIGID CHANNEL LINER

____ PLANTING ____ SOIL RETENTION BLANKET ____ COMPOST MANUFACTURED TOPSOIL SEEDING P SODDING ____ OTHER: (Specify Practice)

2. STRUCTURAL PRACTICES:

(Select T = Temporary or P = Permanent, as applicable)

(Select T = Temporary or P = Permanent, as applicable)

T SILT FENCES	DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
HAY BALES	DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
ROCK FILTER DAMS	DIVERSION DIKE AND SWALE COMBINATIONS
PIPE SLOPE DRAINS	ROCK BEDDING AT CONSTRUCTION EXIT
PAVED FLUMES	TIMBER MATTING AT CONSTRUCTION EXIT
CHANNEL LINERS	STONE OUTLET STRUCTURES
SEDIMENT TRAPS	VELOCITY CONTROL DEVICES
SEDIMENT BASINS	P_ CURBS AND GUTTERS
STORM SEWERS	STORM INLET SEDIMENT TRAP

____ OTHER: (Specify Practice)

3. STORM WATER MANAGEMENT:

I. Storm water drainage will be provided by the ditches, inlets and storm water systems that will carry drainage within the R.O.W.to the low points within the roadway and project site which drain to natural facilities.

2. Other permanent erosion controls include hydraulic design to limit structure outlet velocities and grading design generally consisting of 4:1 or flatter slopes with permanent vegetative cover.

4. STORM WATER MANAGEMENT ACTIVITIES: (Sequence of Construction)

I.Install erosion controls devices (silt fence and inlet protection) 2.Construct roadway and install signals as shown on TCP.

3. Place sodding at disturbed areas.

4.Upon substational completion temporary erosion control devices will be removed.

5. NON-STORM WATER DISCHARGES:

Non-storm water discharges should be filtered, or held in retention basins, before being allowed to mix with storm water. These discharges consist of non-polluted ground water, spring water, foundation and/or footing drain water, and water used for dust control, pavement washing and vehicle washwater containing no detergents.

Design Consultant Logo here - delete block if not applicable



Fort Worth

SECT. JOB HIGHWAY NO 90 119 McCART

STORM WATER POLLUTION PREVENTION PLAN (SW3P)

SHEET 1 OF 2 SHEETS DR[G]NAL DRAW]NG: 09/2002 sw3p-ftw-dgn PROJECT NO. DATE REVISIONS SEE TITLE SHEET 145 NPDES TO TPDES CLARIFY NOTE C.2. ADDED SIGN 2-SHEET FORMAT STATE STATE DIST.NO. COUNTY TARRANT TEXAS FTW

⟨P.E. Seal⟩

Signature

C. OTHER REQUIREMENTS & PRACTICES

MAINTENANCE

All erosion and sediment controls shall be maintained in good working order. If a repair is necessary, it shall be performed at the earliest date possible but no later than 7 calendar days after the surrounding exposed ground has dried sufficiently to prevent further damage from heavy equipment. Disturbed areas on which construction activities have ceased, temporarily or permanently, shall be stabilized within 14 calendar days unless they are scheduled to and do resume within 21 calendar days. The areas adjacent to creeks and drainageways shall have priority followed by devices protecting storm sewer inlets.

INSPECTION:

An inspection shall be performed by a TxDOT inspector every 14 calendar days as well as within 24 hours after any rainfall of one-half inch or more is recorded on a non-freezing rain gauge to be located at the project site, or every 7 calendar days. An Inspection and Maintenance Report shall be filed for each inspection. Based on the inspection results, the controls shall be revised in accordance with the inspection report.

3. WASTE MATERIALS:

Except as noted below, all waste materials shall be collected in a metal dumpster having a secure cover. The dumpster shall meet all state and local solid waste management regulations. All trash and debris from construction shall be deposited in the dumpster. The dumpster shall be emptied, as necessary or as required by local regulation, and hauled to a local approved land fill site. The burying of construction waste on the project site shall not be permitted.

Concrete washout areas shall be required and shall consist of a pit, lined with an impervious material, of sufficient size to contain, until evaporation, all water used and washout material produced during concrete washout operations. The concrete washout locations shall be as directed by the engineer.

Lime slaking tanks shall be surrounded by an earthen berm, capable of containing any overflow.

4. HAZARDOUS WASTE (INCLUDING SPILL REPORTING):

As a minimum, any products in the following categories are considered to be hazardous: paints, acids, solvents, asphalt products, chemical additives for soil staibilization, and concrete curing compounds or additives. In the event of a spill which may be hazardous, the spill coordinator shall be contacted immediately.

SANITARY WASTE:

All sanitary waste shall be collected from the portable units, as necessary or as required by local regulation, by a licensed sanitary waste management contractor.

6. OFFSITE VEHICLE TRACKING

The Contractor shall be required, on a regular basis or as may be directed by the Engineer, to dampen haul roads for dust control, stabilize construction entrances and to remove excess dirt from the roadway.

7. MANAGEMENT PRACTICES:

I. Disposal areas, stockpiles and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any wetland, water body or streambed.

2.Construction staging areas and vehicle maintenance areas shall be constructed by the Contractor in a manner to minimize the runoff of pollutants.


3. All temporary fills placed in waterways shall be built of erosion resistant material.(NWP 14)
4. All waterways shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.

8. <u>OTHER:</u>


I.Listing of construction materials stored on site to be provided by Project Field Office.

2.The Project SW3P File located at the project field office shall contain the N.O.I., CGP Coverage Notice, TCEQ TPDES Form, Signature Authorization, Certification/Qualification Statements, Inspection Reports, Required Maps, and a copy of the TPDES General Permit No.TXRI50000.

STORM WATER POLLUTION PREVENTION PLAN PERMIT POSTING



No Permanent Installation Allowed. Sign to be Removed After Project Completion.



©2019 by Texas Department of Transportation; All Rights Reserved